



M.P. POORV KSHETRA VIDYUT VITARAN Co.Ltd.
OFFICE OF THE CHIEF GENERAL MANAGER (Works)
BLOCK No. 7, III FI, SHAKTI BHAWAN, JABALPUR
CIN No. U40109 MP 2002 SGC105120
Tel: 0761-2702440, Fax: 0761-2660128
gmworksez16@gmail.com



No.EZ/WSW-III/2628

Jabalpur Date: 24.10.2017.

CIRCULAR

Sub:- Guidelines for providing on-line connection under SOUBHAGYA YOJNA with Service cables & Meter departmentally.

Govt. of India has launched a new scheme SOUBHAGYA YOJNA (Pradhan Mantri Sahaj Bijli Har Ghar yojna) to achieve universal household electrification in the country. As per point no. 2.4 of the project guideline it is to mention that the electricity connection to un-electrified household includes provision of service line cable, energy meter including pre-paid / Smart meter, single point wiring, LED lamp and associated accessories in line with technical specifications of construction standards prescribed by REC.

Guidelines for providing on-line connection under SOUBHAGYA YOJNA with Service cables & Meter departmentally is as under:-


- i). Work execution is to be carried out through Registered A or B Class Electrical contractor as per rules.
- ii). Service cables Energy Meter and Earthing Coil will be provided departmentally.
- iii). G.I. Wire, Meter Board, Meter Cutout, Switch Board containing one LED lamp in B.C. Type Holder with 5 Amps Switch, One Mobile charger 3/2 Pin 5 Amps Socket with Switch and Wiring for consumer connection will be provided by the Electrical Contractor.
- iv). Regarding payment of Labour charges and cost of material is to be paid to the contractor. Materials provided by contractor as per actual, shall be verified by field officer. Contractor's bill is to be prepared by contractor along with labour and transportation charges as per estimate. Contractor shall submit bills monthly to OIC/Feeder Incharge for verification. Further bills will be submitted to concerned AE to EE for passing. Bills must reach within 5th of every month to concerned RAO, so that same can be included in monthly requirement to avoid delay in payment.
- v). Estimate will be prepared as per current schedule of rates for actual distance & as per actual survey. Sample Schedule of estimate is under :-

(A) Material to be provide by the EZ Discom as per SoR-2016-17:-

SN	Particulars	Unit	Rate (Rs.)	Qty.	Amt (Rs.)
1	2	3	4	5	6
1	Single phase Electronic meter with data downloading facility & box 5-30 Amps.	No.	849	1	849
2	Earthing Coil of 115 Turns of 50MM Dia and 2.5 Mtrs lead of 4.0 MM GI Wire. (For consumer earth)	No.	104	1	104
3	PVC insulated, 1100 Volts Grade Armoured Al. Cable 2.5 Sq.mm. (two core)	Mtrs	28	35	979.86
	Total				1828.86
4	Centages :				
	(i) Stores incidental charges	2.5%			
	(ii) Contingencies	5.0%			
	(iii) W/c. Establishment	2.5%			
	(iv) T & P	1.5%			
				11.50%	210.32
5	Labour charges				182.87
6	Transportation charges				182.87
7	GST as per prevailling rules. on Labour charges & Transportation charges @ 18%				65.84
8	Grand Total				2470.79

(B) Materials to be provided by the Contractor:

SN	Particulars	Unit	Rate (Rs.)	Qty	Amt (Rs.)
1	3	4	5	6	7
1	10 SWG GI tension wire	Kg.	58.00	3	174.00
2	Service line support of Angle 40x40x5 MM, 3.5 Mtrs long.	Mtr.	65.00	3.5	227.50
3	Piano type ISI marked 250V/5A switch.	No.	10.00	2	20.00
4	250V/5A ISI marked BC Type Batten holder	No.	10.00	1	10.00
5	1.5 sqm copper multistrands PVC insulated ISI marked cable,	Mtr.	10.00	10.00	100.00
6	Kit Kat 16 Amps.	No.	56.00	1	105.00
7	10mm dia earth terminal point,	No.	10.00	1	10.00
8	12mm dia PVC rigid pipes including its clamps, fittings and fixtures as required	Mtr.	12.00	5	54.84
9	9 Watts pin type LED lamp, 144-288 Volts operating voltage range	No.	65.00	1	65.00
10	LT Shakle insulator 65x50mm with hard ware	No.	15.00	2	30.00
11	ISI marked Insulating tape as required	No.	10.00	1	10.00
12	ISI mark, 5A-240V, three & Two pin 5 Hole socket.	No.	10.00	1	10.00
13	Fiber Glass Reinforced Polyester sheet moulding compound (SMC) Board for Light Point fitting 200X150X28 mm (Mnimum)	No.	70.00	1	70.00
14	Clips for supporting the pipes at every 1 feet distance	No.	1.00	90	90.00
15	Sundries as PVC Grouting Plugs, Steel Screw, MS Grouting Bolt for service line support etc.	LS			100.00
16	TOTAL of supply				1238.32
17	Labor & Erection Charges				
18	I) for meter fixing				132.00
19	II) for Service line				250.00
20	Total of Labor & Erection				382.00
21	GST as per prevailling rules. 18% on Labor & Erection				68.76
22	Total amount of the Estimate S.No. 8 of Sch (A)+ S.No.16+20+21 of Sch (B).				4159.87


Chief General Manager (Works)
MPPKVV Co. Ltd., Jabalpur

- Copy to:-**
- 1) CGM, (HR&A)/RAPDRP/ RGGVY/FS/ADB/Pur/Comml. MPPKVV Co. Ltd, Jabalpur.
 - 2) CFO, MPPKVV Co. Ltd, Jabalpur.
 - 3) CE(JR/SR/RR)/(Store), MPPKVVCL, Jabalpur/Sagar/Rewa.
 - 3) SE, (City/O&M) Circle, MPPKVV Co. Ltd, _____
 - 4) GM, Safety/Head IT, MPPKVV Co. Ltd, Jabalpur.
 - 5) EE, (City/O&M)/Stores/STM/STC/MTRU, MPPKVV Co. Ltd, _____
 - 6) Sr.A.O./RAO MPPKVV Co. Ltd, _____
 - 7) PS to MD-EZ, MPPKVV Co. Ltd, Jabalpur.